



City of  
**Los Banos**  
*At the Crossroads of California*

**ADDENDUM NO. 1**

June 2, 2016

**F STREET STORM LINE**

1. This Addendum forms a part of the Bidding Documents and will be incorporated into the Contract Documents, as applicable. All other conditions of the Contract Documents remain unchanged. The following changes, additions, or deletions as set forth herein shall apply to the Contract Documents and shall be made a part thereof and shall be subject to all the requirements thereof as through originally shown and/or specified.
  
2. The Contract Documents are hereby modified to effect the following changes:
  - a) Bid, Bid Schedule Item No. 9 has been revised to indicate the correct size water line. **Replace Bid Schedule with attached Revised Bid Schedule.**
  - b) Special Provisions, Note 24. Bid Item Descriptions. Bid Item No. 9 has been revised to read as follows:  
*"Bid Item No. 9 – Install 10-Inch C900 Waterline (Including Trenching & Backfill):*  
*This item shall be bid, measured and paid on a per-linear-foot basis. Payment shall include full compensation for furnishing all labor, materials, tools and equipment to install 10" C900 water pipe by conventional open trench method, including, but is not limited to, trenching, bedding, thrust blocks, backfilling, ground restoration, compaction, temporary pavement restoration, and all incidentals, complete in place, as shown on the plans, and in accordance with these specifications, the Standard Provisions and the Standard Specifications, and as directed by the Engineer."*
  
3. Bids shall be submitted in accordance with this Addendum. All Bidders MUST acknowledge receipt of this Addendum by signing and returning this Addendum with your bid.

City of Los Banos

By: Mark Fachin, PE  
Public Works Director/City Engineer

Firm Name: \_\_\_\_\_

By: \_\_\_\_\_

Title: \_\_\_\_\_

Date: \_\_\_\_\_

**Bid Schedule  
For  
F STREET STORM LINE**

Bidder agrees to perform all the work described in the Contract Documents for the following unit and lump sum prices and understands that the quantity of work shown is approximate only. The schedule shall be completed by the bidder with the unit and lump sum prices entered in numerals. The extensions shall be made by the bidder. In case of discrepancy between the unit prices and the extension thereof, the unit price shall be considered as correct when evaluating bids.

ITEM NO.	ITEM	QUANTITY AND UNIT		UNIT PRICE	AMOUNT
1	Mobilization/Demobilization	1	LS	\$ _____	\$ _____
2	Remove Existing Pavement/Concrete (Including Sawcut/Grinding)	5,025	SF	\$ _____	\$ _____
3	Remove Existing Storm Drain Line	14	LF	\$ _____	\$ _____
4	Remove Existing Storm Drain Catch Basin	3	EA	\$ _____	\$ _____
5	Abandon Existing Storm Drain Manhole	1	EA	\$ _____	\$ _____
6	Remove Existing Water Line	28	LF	\$ _____	\$ _____
7	Erosion Control	1	LS	\$ _____	\$ _____
8	Traffic Control and General Safety	1	LS	\$ _____	\$ _____
9	Install 10-Inch C900 Waterline (Including Trenching, Thrustblocks & Backfill)	28	LF	\$ _____	\$ _____
10	Connect to Existing Water Line	2	EA	\$ _____	\$ _____
11	Install 18-Inch Storm Drain Line (CL200, C-900)	928	LF	\$ _____	\$ _____
12	Install 12-Inch Storm Drain Line (CL-200, C-900)	158	LF	\$ _____	\$ _____
13	Install Storm Drain Manhole	4	EA	\$ _____	\$ _____
14	Install Storm Drain Catch Basin, Type A	3	EA	\$ _____	\$ _____
15	Connect to Existing Storm Drain Manhole	1	EA	\$ _____	\$ _____
16	Connect Storm Drain Lateral to Existing Catch Basin	2	EA	\$ _____	\$ _____
17	Curb & Gutter (Including Returns)	65	LF	\$ _____	\$ _____

ITEM NO.	ITEM	QUANTITY AND UNIT		UNIT PRICE	AMOUNT
18	Concrete Sidewalk (Including Ramps & Returns)	418	SF	\$	\$
19	Accessible Ramp (Labor and Truncated Domes Only)	2	EA	\$	\$
20	Trench Patch AC Pavement	4,511	SF	\$	\$
21	Striping (Crosswalk Lines, "STOP" Legend, and Red Curb)	1	LS	\$	\$
<b>TOTAL:</b>				\$	

Note: The representations made herein are made under penalty of perjury. Any information contained in the bid which is proven false shall be considered nonresponsive and this bid shall be rejected.